





ITER Construction - Plant System Integration -

Summer Schools
23 July, 2008

Prepared by E. Tada (ITER)
Presented by S. Matsuda (JAEA)





ITER Construction

- Plant System Integration -

- **International Cooperation**
- **Integral Project Management**
- **System Integration**
- **Site and licensing preparation**
- **Summary**


The Tokamak

"тороидальная камера в магнитных катушках"
(toroidal'naya kamera v magnitnykh katushках) — toroidal chamber in magnetic coils (Tochamac)).

The major toroidal magnetic confinement configuration

The Tokamak:

- operationally, is essentially an **electrical transformer**
- **toroidal** magnetic field is produced by external magnetic field coils
- plasma current produces **poloidal** magnetic field
- result is a set of nested **helical surfaces**
 ⇒ **plasma confinement**





Central Solenoid
Nb₃Sn, 6 modules

The core of ITER

Toroidal Field Coil
Nb₃Sn, 18, wedged

Poloidal Field Coil
Nb-Ti, 6

Major plasma radius 6.2 m


Plasma Volume: 840 m³

Plasma Current: 15 MA

Typical Density: 10²⁰ m⁻³

Typical Temperature: 20 keV

Fusion Power: 500 MW



Cryostat
24 m high x 28 m dia.

Vacuum Vessel
9 sectors

Blanket
440 modules

Port Plug
heating/current drive, test blankets limiters/RH diagnostics

Torus Cryopumps, 8

Divertor
54 cassettes

Machine mass: 23350 t (cryostat + VV + magnets)


- shielding, divertor and manifolds: 7945 t + 1060 port plugs

- magnet systems: 10150 t; cryostat: 820 t



ITER - International Cooperation

Construction & operation by the ITER Organization (IO) with support of the Domestic Agencies (DAs) of the seven parties



IO: Management & integration (Nuclear operator)
DAs: In kind contribution & procurement



 ITER Partners




Construction Sharing

Complex plant system with advanced technology

Sharing: EU 5/11, other six parties 1/11 each


90 % in kind procurement





Procurement In Kind

Involvement of the parties in key fusion technology areas
A fair sharing of the cost of the device by 'value' and not by currency
Interfaces management and integration by IO






General Roles & Responsibilities for Construction

- ITER IO
 - Planning/Design
 - Integration / QA / Safety / Licensing / Schedule
 - Installation
 - Testing + Commissioning
 - Operation
- Parties – DAs
 - Detailing / Designing
 - Procuring
 - Delivering
 - Support installation
- IO and DAs plus Fusion Community work together on exploitation of ITER. ITER IO coordinates and participates in the program (e.g. Test Blanket Module program for power generation).



ITER Organization



Revised on 15 May 2008



Domestic Agencies

- **China:** ITER China Office is acting as DA which will be formally established soon.
- **EU:** F4E (Fusion for Energy) was established as DA in Barcelona.
- **India:** Indian ITER Office to be established with the Institute for Plasma Research to function as DA.
- **Japan:** JAEA (Japan Atomic Energy Agency) was appointed as its DA.
- **Korea:** ITER Korea was established within the NFRI (National Fusion Research Institute).
- **Russia:** A special department was established within the Kurchatov Institute to function as its DA.
- **US:** ITER Project Office was established in the ORNL.



Integral Project Management

- **Baseline: scope, schedule, cost & management -**

- **Technical scope**

Reference Design elaborated through R&D in the design phase and up-to-date design review with the DAs and fusion community

- **Schedule**

First plasma in middle of 2018 as a reference, consistent with the procurement schedules in the DAs

- **Cost**

Bottom-up estimate to achieve scope and schedule

- **Management**


Management systems/tools for project execution to achieve the technical scope within schedule and cost.

Key Technology Development in the Design Phase




CENTRAL SOLENOID MODEL COIL

Radius 3.5 m
Height 2.8m
 $B_{max}=13\text{ T}$
0.6 T/sec



TOROIDAL FIELD MODEL COIL


Height 4 m
Width 3 m
 $B_{max}=7.8\text{ T}$




BLANKET MODULE
HIP Joining Tech



REMOTE MAINTENANCE OF DIVERTOR CASSETTE
Attachment Tolerance $\pm 2\text{ mm}$



DIVERTOR CASSETTE AND PFCs
 20 MW/m^2




VACUUM VESSEL SECTOR

Double-Wall,
 $\pm 5\text{ mm}$




REMOTE MAINTENANCE OF BLANKET
4 t blanket sector $\pm 0.25\text{ mm}$






Reference Project Schedule





Baseline Document Structure

- Categorized to define scope, schedule, cost and management plan
- Layered for the approval authority, corresponding to the organization structure: Council, Management (DG/PDDG) and Departments (DDGs)
- Integrated into Procurement Arrangement for construction





Integral Management

Project Plan and Resource Estimate (Council level doc.)

- Overall project schedule & construction schedule
- Management systems for the project execution
- Work plan and resources for construction

MQP (Management level doc.)

- Cost & Schedule Management (Earned Value Management)
- Configuration Management – change control
- Procurement management – in-kind procurement by DAs
- Risk Management – avoidance, reduction and mitigation
- Quality Assurance – graded approach based on importance

Detailed Procedures & PA (Department level doc.)



Earned Value Management (EVM)



- Schedule & Cost Control -

Schedule Performance: Earned Value vs. Planned Value

Cost Performance: Earned Value vs. Actual Costs

Schedule performance tracking for in kind procurement:


- Milestones defined in PA: measurable/verifiable deliverables
- Credit attributed (IUA) to each milestone
- Milestone achievement: acceptance and then credit allocation





Configuration Management

Configuration Management is the process for establishing and maintaining consistency of a product's performance, functional and physical attributes with its requirements, design and operational information throughout its life.



Main Elements:

- Identification of the configuration baselines
- Management of the Design Requirements
- Management of the Design Changes



Management of Design Requirements

The PS defines the operational features and performance required to fulfil the ITER mission.




The PR translates the top level mission requirements into engineering terms.



The SRDs define the requirements for the systems.

PS : Project Specification
PR : Project Requirement
SRD: System Requirement Document





Design Change Management

Changes categorize and approved depending on the level of impact:


Level 0: ITER Council

Level 1: ITER DG/PDDG

Level 2: ITER DDGs

Level 3: DAs

- Change request (PCR) to be generated and reviewed in terms of impact on scope, schedule and cost
- Changes to be managed by Configuration Control Board (CCB)






Risk Management

Primary Objective of the ITER Risk Management is to provide a sustainable and consistent process for the management of cost, schedule, technical, and operational uncertainty on the project.


Execution Components



Possible Risk Areas




Overall Work Relationship for System Integration





System Engineering Process


ITER System Engineering plan to define engineering processes and clarify roles & responsibilities for integration. It focuses on needs and functionality in the early stage and then integration and verification.





ITER Construction Life Cycle

	ITER-IO			ITER-DAs			ITER-IO	
	Conceptual design	Layout & analysis	Detail design	Technical spec	Manufact.	As built	Acceptance	Installation
Built-to-print	Red	Red	Red	Red	Green	Green	Red	Red
Detail design	Red	Red	Green	Green	Green	Green	Red	Red
Functional spec	Red	Green	Green	Green	Green	Green	Red	Red





Interface Management

System Interface Control among systems Procurement Interface Control among DAs

PBS	11	15	16	17	18	22	23	24	26	27	31	32	34	41	43	45	46	51	52	53	54	55	56	61	62	63	64	65
Magnets	11	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•					•		•	•			
Vacuum Vessel	15	•	•	•	•	•	•	•	•	•	•	•	•			•			•	•	•	•	•	•	•	•	•	•
Blanket systems	16	•	•	•	•	•	•	•	•	•	•	•	•						•	•	•	•	•	•		•	•	
Divertor	17	•	•	•	•	•	•	•	•	•	•	•	•										•		•	•		
Fuelling & wall conditioning	18	•	•	•	•	•	•	•	•	•	•	•	•		•	•	•			•					•	•		•
Machine Assembly & tooling & installation	22	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•		•	•	•	•	•	•	•	•	•	•
Remote Handling equipment	23	•	•	•	•	•	•	•	•	•	•	•	•		•	•	•		•	•	•	•	•	•	•	•	•	•
Cryostat	24	•	•	•	•	•	•	•	•	•	•	•	•		•	•	•					•			•	•		
Cooling water system	26	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•		•	•	•	•	•	•	•	•	•	•
Thermal shield	27	•	•	•	•	•	•	•	•	•	•	•	•										•		•	•		
Vacuum	31	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•		•	•	•	•	•		•	•		•
Tritium plant	32	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•						•				•	
Cryoplant & cryodistribution	34	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•							•	•	•		•
Coil power supplies & distribution	41	•				•		•					•	•	•	•	•								•	•	•	
Steady state electrical power network	43	•				•	•	•	•	•	•	•	•	•	•	•	•		•	•	•	•	•	•	•	•	•	•
CODAC	45	•	•			•	•	•	•	•	•	•	•	•	•	•	•		•	•	•	•	•	•	•	•	•	•
Safety & interlock systems	46	•				•	•	•	•	•	•	•	•	•	•	•	•	•		•	•	•	•	•	•	•	•	•
Ion cyclotron H&CD system	51	•	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•
Electron cyclotron H&CD system	52	•	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•
Neutral Beam H&CD system	53	•	•	•		•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•
Lower Hybrid H&CD system*	54	•	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•
Diagnostics	55	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•
Test blankets	56	•	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•
Site	61	•	•			•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•
Reinforced concrete buildings	62	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•
Steel frame buildings	63					•		•					•	•	•	•	•							•	•	•	•	•
Radiological protections	64	•	•	•		•					•			•	•	•	•							•	•	•	•	•
Liquid and gas distribution	65				•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•



RAMI: Reliability, Availability, Maintainability & Inspectability


RAMI: Technical Risk Control program for the success and availability of ITER. The ITER RAMI program is declined in 4 stages:

- A classical Functional Analysis to identify the main functions and their possible Failures.
- An analysis of the failure modes, their cause & effects and the establishment of a Critical List according to their importance with respect to the machine operation availability (FMEA).
- Evaluation of Severity, Occurrence and Detectability levels of main failure mode causes: Criticality = S.O.D (FMECA).
- As a function of this criticality level, the risk of a failure can be considered as acceptable or not. When the risk level is too high, measures are to be taken for improvement of Design, Fabrication and Testing to reduce the risk level, and/or for an optimized Preventive Maintenance Plan and an adapted Spare Part Strategy.

Basic Safety Approach

- Confinement of Radioactive Material -

Based on the unique safety features, the safety goal will be achieved by a combination of enclosure containing radioactive material and vent/clean-up system for mitigating the consequence in case of failure of enclosure.



Port cell & vault

1st Confinement System

- Vacuum vessel
- VV extensions
- etc

2nd Confinement System


- Port cells
- Vaults
- etc

Dynamic Systems



- Vent & cleanup system
- etc

Codes and Standards Application

Internationally recognized codes & standards can be applied for construction but the compliance with nuclear regulation should be justified for the safety important components.








Subassembly of the Integrated Machine Sectors




Subassembly 9 sectors with 2 tools

- 2 x TFCs
- VV sector
- VVTS sector
- port shrouds


ITER Vacuum Vessel



Assembly Operations in Tokamak Complex



**Subassembly of
TF Coil/VV Sector
~1400 ton**



Assembly in Pit



Site and Licensing Preparation



Plan of ITER Site Layout

Magnet power
convertors buildings

Cryoplant
buildings

Hot
cell

Tokamak
building

Tritium
building



Cooling
towers

- Will cover an area of about 60 ha
- Large buildings up to 170 m long
- Large number of systems



Site Preparation & Construction Permit

- The main platform-levelling work commenced on the ITER site.
- Preparations for the construction of the PF coil winding building are under way.
- The 2007 critical path design activities for civil, mechanical and electrical engineering were finished.
- The building construction permit was granted in April.



ITER Tokamak Building





Site Preparation Status

Site New Entrance



Platform view, 25% completed



Contractor Area (~500 people) and JWS 2




Licensing Process

- On 31 January 2008, the safety files (DAC), including the Preliminary Safety Report, in application of the TSN law, were finished and sent to the French Nuclear Authorities.
- Examination of the files are ongoing and the Public Enquiry is foreseen around the end of 2008 or early 2009.
- The issuance of DAC could be expected after the formal examination by the so-called *Groupe Permanent*.
- The following steps in the licensing procedure are related to the authorization for starting to operate with radioactive fuel.





Summary





Together with us

